



18/22/25mm NSF adjustable shelves
 Carpet removed/re-laid by others prior to/after our delivery.
 Existing painting cut/removed to install our work.
 Curtains if any fitted, adjusted to suit our design, works by others after our installation.
 Existing wires removed & made good by others prior to our installation.
 One adjustable shelf provided in each cupboard.
 Provide pencil grooves over inlets.
 Cut for sensors etc on site if/as required & drilled but only repair as is provided in our estimate.

Cut out back for ventilation and wires in cupboard for CPU.
 Power cable, TV, BT, Intruder Alarm etc and all electrical works etc to be removed/replaced as required, works by others prior to/after our installation.
 Cut additional holes in wall-top for wires.
 Lights, power and all equipment supplied and fitted by others after our delivery.
 Existing power etc to be removed/replaced by others prior to/after our delivery to clear our work and below inlets (and fixed shelf) for easy access.
 Existing radiator and cover to be removed and re-fitted adjacent to sofa bed, no provision made for cover under our basecase, radiator to be clear of our works as set out in the design.

Worked for customer's own supply and fit after our installation unless sent to our premises prior to delivery/commence when we will fit.
 Answer/effort access.
 Terms and Conditions and those in Estimate Specifications apply.

