



Entrance.

- 18/22mm MDF adjustable shelves 2 off inside each cupboard.
 - 80mm fixed shelves as drawn unless otherwise specified and agreed on ordering.
 - To go onto polished floor.
 - Existing skirting cut/removed to install our works
 - Some shelves or cupboards may be altered in depth as/IF specified and agreed on ordering.
 - One adjustable shelf provided in each cupboard.
 - Provide touch magnetic chatches to cupboard doors except CD cupbd.
 - Cut for wire/power etc on site if/as required & directed but only insofar as is provided in our estimate.
 - Cut out back for ventilation and wires for alcove cupboard to take Flat screen TV equipment.
- Power cable, TV, BT, Intruder Alarm etc and all electrical works etc to be removed/resited as required; works by others prior to/after our installation.
 - Cut additional holes in waist-top for wires on site if/as required.
 - Lights, power and all equipment supplied and fitted by others after our delivery.
 - Existing radiator and pipework to be removed, resited or replaced clear of our works, as set out in the design, by others prior to our installation
 - Handles, if required, for customer's own supply and fix after our installation unless sent to our premises prior to delivery/collection when we will fix.
 - Terms and Conditions and those in Estimate Specifications apply
 - Part access thru window.